


## Important Technical Data

Minimum operating pressure 1.0 bar (tap)  
Maximum operating pressure 5.5 bar\* (tap)  
Maximum operating pressure 2.0 bar\* (spray)

Maximum hot water temperature 70°C\*  
Recommended hot water temperature 46°C

Note: If these temperatures or pressures are exceeded, even for short periods, damage can result. In these instances a thermostatic mixing or pressure reducing valve should be installed.



Abode taps use WRAS, KIWA, NSF or recognised approved components or are manufactured in accordance with recognised European or international standards. Please ensure that your Abode Kitchen mixer is fitted in accordance with Local Water Byelaws.

These installation guidelines have been prepared for your direction and you must exercise due care at all times. We do not accept responsibility for problems that may occur through improper installation. Whilst assembling the tap take care not to accidentally loosen any screwed assemblies.

Abode is a registered trademark of Abode A division of Norcros Group (Holdings) Limited

## Manufacturers Product Reference

5656

©Abode  
11/2017

abode

Unit L, Zenith Park, Whaley Road,  
Barnsley,

S75 1HT.

Tel: 01226 283434 Fax: 01226 282434

www.abode.eu

All errors and omissions excepted.

*Bayenne Bridge  
with independent  
spray*



## 5 Year Warranty, Terms And Conditions

In the unlikely event that you should experience any defect in the materials or workmanship of your new Abode mixer within 5 years of purchase, the purchaser's sole remedy shall be the replacement (at the manufacturer's discretion) of all or any part of the product that is defective. All working parts and valves are guaranteed for a period of 5 years from purchase. Decorative surface finishes and O-rings are guaranteed for 1 year from the date of purchase provided that our advice concerning care has been observed and no scouring agents have been used. This is provided that the mixer or tap has been used for normal domestic purposes and that the care, installation and maintenance instructions have been observed. The warranty extends to the original purchaser only.

Marks, scuffs and scratches caused by improper installation or accidental damage are not covered by this guarantee. Neither are shade variations or any damage or defect caused by incorrect installation or abuse of the fitting.

As we are continuously improving and developing our range of products, finishes & colours, in the event of a valid claim, we may not be able to provide an identical replacement for the defective product throughout the guarantee period. Where an identical product is no longer available, we will supply the nearest equivalent from our then current product range. In assessing your claim, we must be given the opportunity to inspect the product as installed prior to removal. Any product returns must be packaged as received and complete.

No other warranties, express or implied, are made, including merchantability or fitness for a particular purpose. Under no circumstances shall the manufacturer be liable for any loss or damage arising from the purchase, use or inability to use this product, or for any special, indirect, incidental or consequential damages. No liability is accepted for consequential damage to other household fixtures, fittings or furnishings arising from this claim, even if attached to the product. No installer, dealer, agent or employee of Abode has the authority to modify the obligations or limitations of this warranty.

**Please leave these instructions for your customer.**

## Parts and Contents:

Key	Description	Qty
A	Mixertap body	1
B	Upper rubber washers	2
C	Inlet legs (with integral non return valves )	2
D	Lower rubber washers	2
E	Metal washers	2
F	Fixing nuts	2
G	½" BSP adaptor	1
H	M15 adaptor	1
I	15mm washer	1
J	Nylon pull out hose ½"	1
K	Fixing nut	1
L	Metal washer	1
M	Rubber washers	2
N	Sprayhead body	1
O	Pull out hose nut	1
P	Rubber washer	1
Q	Non return valve (internal to sprayhead)	1
R	Sprayhead	1

## Installation Preparation:

All parts should be removed from their packaging and inspected for any transport damage prior to installation. You should check you have the required hot and cold supply pressure also.

Before installing the new mixer it is essential that you thoroughly flush through the supply pipes in order to remove any remaining solder, swarf or impurities from your system. Failure to carry out this simple procedure could cause problems or damage to the workings of the mixertap.

We recommend installing particle filters and isolation valves to both the hot and cold feed pipes in an accessible position. This will help to prevent premature failure of the valves and ease any future maintenance.

Shut off your water heating system and ensure that your mains stopcock is closed. Open the lowest hot and cold taps in the house and allow the water to run until the cold-water storage tank and pipes are fully empty. Please note, the hot water storage cylinder (if applicable) may remain full.

This mixertap requires a 3 x 35Ømm tap holes, the nominal centre spacing is 203mm. If replacing an existing tap, remove the tap & clean the end of the feed pipes using wire wool the tap hole area should be free from dirt and sealant.

Loosely position the tap and tail pipes to check if any alteration to the existing pipework is required, if this is the case do this now.

If placing the tap or spray through a worktop for example the tap hole should be sealed in accordance with the worktop manufactures instructions, you should pay particular care that the seal between the worktop and the tap is correctly seated.

The installation of this product should respect requirement IRN R090.

## Installation:

1. Pass the upper rubber washers (B) onto the inlet legs (C) flush to the tap base (A).
2. Pass the inlet legs (C) through the tap holes. Now pass the lower rubber washers (D), metal washers (E) then fixing nuts (F) onto the inlet legs (C).
3. Whilst holding the tap (A) and legs (C) in place on the tap hole, loosely tighten the fixing nuts (F).
4. Fully tighten the fixing nuts (F) fixing the tap into position.
5. Connect the hot and cold inlet legs (C) to the water mains using ½" BSPx15mm compression fittings. Note: Non-return valves are factory fitted internally into inlet legs (C).
6. Push the (upper) rubber seal (M) onto the sprayhead body (N), then pass the sprayhead body (N) through the 3<sup>RD</sup> tap hole, now pass the (lower) rubber washer (M), then metal washer (L) over the sprayhead body (N).
7. With the sprayhead body (N) central to the 3<sup>RD</sup> tap hole tighten fixing nut (K) onto sprayhead body (N) to fix its position.
8. Screw the hose nut (O) onto the sprayhead (R) ensuring that rubber seal (P) is present in the joint.
9. Pass the pull out hose (J) through the top of the sprayhead body (N), screw the pull out hose (J) to the M15 adaptor (H) ensuring that 15mm washer (I) is present in the joint.
10. Screw the ½" adaptor (G) to the cold water supply pipe. Nb. we recommend an additional service valve on the spur to control the spray flow rate.

## After Installation:

Once you have visually checked the installation of the new tap and all connections, ensure that all other fittings are closed except the new tap which should be left open. Turn on your water heating system and ensure that your mains stopcock is open. Reconnect both the hot and cold water supplies to this fitting. Check the function of flow and function of hot, cold and mixed water.

Turn off the tap and check carefully for any leaks around all connections on the fitting and adjoining plumbing. If possible return to the installation after a longer period to double check for slower leaks. If pressure testing equipment is available check the installation to the maximum recommended pressure.

Clean the tap to remove any marks created during installation as instructed then place a bag over the product to protect the tap until it is ready for use. The installation should be periodically checked for damage, if the property is left unattended for a prolonged period we recommend isolating water supplies.

## Care Instructions For Your Kitchen Sink Tap:

To maintain the appearance of this product, **ensure that it is regularly cleaned only using a clean, soft damp cloth.** A solution of warm water and a mild liquid detergent may be used where necessary, and then the fitting rinsed thoroughly and wiped dry. **Any other cleaning action will invalidate your warranty.** If the mixertap has a diffuser it should be unscrewed and cleaned periodically in water.

Abrasive cleaners, scouring cleaners and acidic cleaners must not be used under any circumstances. Avoid contact with all solvents (including chlorinated solvents, ketones or acetones as these may result in surface deterioration or etching). Also avoid contact with any harsh household chemicals such as oven cleaners, drain cleaners, rust removers, paint strippers and toilet bowl cleaners, bar keepers friend or Brasso.

